





東莞漫亞
五金製品有限公司
Dongguan Manya
Hardware Products Company Limited



漫亞插式法蘭



漫亞插式法蘭生產線



插式法蘭測試報告

Model:M-120

Campbell Shillinglaw Lau Ltd
金寶聲學環保顧問有限公司

On Ref: CSL011-2009/096044

REPORT ON DEFLECTION AND AIR LEAKAGE OF DUCTWORK TEST TO DW144 (SPECIFICATION FOR SHEET METAL DUCTWORK 1998) FOR MEDIUM PRESSURE SYSTEM ON MYG-120 SLIDE ON FLANGE DUCT JOINTING SYSTEM (CLASSIFICATION TO TMI 1987)

DATE: 8, 21 May 2009
TESTED BY: Mr. Wilson LEUNG & Mr. YALE WANG (CSL)
REPORT BY: Mr. YALE WANG (CSL)
SECTOR OF TEST: MYG INTERNATIONAL LTD.
TEST LOCATION: WASHIA CENTRE ROAD, LANGSHA INDUSTRIAL AREA, DONGGUAN TOWN, DONGGUAN CITY, PRC.

File A 102, Wilson Commercial Building, 22-24 Pao Avenue, Tin Tin Tsai, Kowloon, Hong Kong
香港九龍彌敦道22-24號金寶聲學環保顧問有限公司
34 號 2002-2003 室 電話: 8522 281 6184 傳真: 8522 281 6184 0000

1. INTRODUCTION

Campbell Shillinglaw Lau Limited were commissioned by MYG International Ltd. to carry out duct deflection behavior and air leakage test on their MYG-120 slide on flange duct jointing system in accordance with DW144 (specification for sheet metal ductwork 1998) and TMI (1987).

2. TEST APPARATUS

a) The Test apparatus consists primarily of the following:-
i) A centrifugal flow fan
ii) A bypass damper
iii) A U-tube manometers giving readings of the differential pressure between the sheet metal duct assembly and the ambient.
iv) A flexible hose connecting the connecting the fan-duct assembly to the sheet metal duct.
v) A dial gauge giving readings of 0.01mm resolution and a maximum traverse of 25mm.
vi) An Electronic Manometer LMI measures and digitally displays the duct pressure and the corresponding inlet flowrate to sustain the duct leakage.

The overall experimental set up is as shown in 090604G, 090604O and the detail set up for the deflection measurement is as shown in 090604L.

3. TEST SAMPLE

The test specimen of the following dimension, 090604A, were constructed:
Specimen: 2480mm(L) x 1000mm(W) x 350mm(H)
(Rated to J2 medium pressure)

The test sample consists of a rectangular duct (0.8mm thick) which was prefabricated by pittsburg lock seam, 090604H, and ready for duct section assembly.

The MYG-120 flange (090604L) was made by an ACL machine. The production detail and assembling of the flange are described in appendix I.

The MYG-120 slide on flange was fastened to the duct section to form a cross joint by spot welding at 50mm from corners and 300mm o.c. for the rest. Configuration of the flange joint, the sheet metal duct and the G-clamp are as shown in 090604L.

4. RESULTS

4.1 Test Result of deflection

Dial Gauge Reading	Specimen	Pressure Pa								
		0	300	1000	3000	5000	8			
		0	1.7	2.8	4.1	3.8	1.8	0.1	2.8	4

N.B. The allowable deflection is in accordance to TMI and equal to 1/250 of width.

4.2 Test Result of air leakage


Duct Size Width (mm)	Pressure (Pa)	Square Area (Sq. Meter)	Test Leakage (L/min/Sec)	Max. Allowed Leakage (L/min/Sec)
1000 x 250	1000	0.25	1.88	2.08

N.B. The allowable air leakage is in accordance to TMI and equal to 40% of maximum permitted loss for the appropriate pressure class, as indicated in Table 17 of DW144.

5. CONCLUSION

As shown in section 4 "Results", test specimen does not exceed the deflection and air leakage requirement of DW144 (specification for sheet metal ductwork 1998) and TMI (1987) as stipulated.

CHECKED BY: *Leslie Lau*
For and on behalf of Campbell Shillinglaw Lau Ltd.





東莞漫亞
五金製品有限公司
Dongguan Manya
Hardware Products Company Limited



插式法蘭測試報告

Model:M-130

Campbell Shillinglaw Lau Ltd
金寶聲學環保顧問有限公司

Our Ref: CSL01-2009090902

REPORT ON DEFLECTION AND AIR LEAKAGE
OF DUCTWORK TEST

TO

DW144 (SPECIFICATION FOR SHEET METAL DUCTWORK 1998)
FOR MEDIUM PRESSURE SYSTEM

ON

MYG-130 SLIDE ON FLANGE DUCT JOINTING SYSTEM
(CLASSIFICATION TO TME 1987)

DATE : 4, 21 May 2009
TESTED BY : Mr. Wilson Leung & Mr. Yale Wang (CKL)
REPORT BY : Mr. Yale Wang (CKL)
SPONSOR OF TEST : MYG INTERNATIONAL LTD.
TEST LOCATION : MYG FACTORY
WANG CHING ROAD,
LACHINA INDUSTRIAL AREA,
DANG TUI TOWNSHIP,
DONGGUAN CITY,
PRC

File A 133 - Value Commercial Building, 21-24 The Avenue, Hui Shu Tsz, Hui Shu Tsz, Hui Shu Tsz, Hong Kong
香港新豐街21-24號匯富商業中心1樓A133
Tel: 852 (912) 2158 9021 Fax: 852 (912) 2817 8181 Email: cs@campbellshillinglaw.com.hk

1. INTRODUCTION

Campbell Shillinglaw Lau Limited were commissioned by MYG International Ltd to carry out duct deflection behavior and air leakage test on their MYG-130 slide on flange duct jointing system in accordance with DW144 (specification for sheet metal ductwork 1998) and TME (1987).

2. TEST APPARATUS

a) The Test apparatus consists primarily of the following:-
i) A centrifugal flow fan
ii) A bypass damper
iii) A U-tube manometer giving readings of the differential pressure between the sheet metal duct assembly and the ambient.
iv) A flexible hose connecting the manometer to the sheet metal duct.
v) A dial gauge giving readings of deflection resolution and a maximum reverse of 25mm.
vi) An Hachette Manometer LM1 measures and digitally displays the duct pressure and the corresponding inlet flow rate to maintain the duct linkage.

The overall experimental set up is as shown in 0906041, 0906040 and the detail set up for the deflection measurement is as shown in 0906046.

3. TEST SAMPLE

The test specimen of the following dimension, 0906040, were constructed:
Specimen: 2480mm(L) x 1400mm(W) x 500mm(H)
(Fixed to 24 medium pressure)

The test sample consists of a rectangular duct (1.5mm thick) which was prefabricated by spotweld lock seam, 0906041, and ready for duct section assembly.

The MYG-130 flange (0906046) was made by an ACL machine. The production detail and assembling of the flange are described in appendix 1.

The MYG-130 slide on flange was fixed to the duct section to form a cross joint by spot welding at 50mm from corner and 30mm etc. for the rest. Configuration of the flange joint, the sheet metal duct and the U-tube are shown in 0906046.

4. RESULTS

4.1 Test Result of deflection

Duct Design Pressure	Specimen #	Pressure Pa						Calculated deflection at 100Pa (mm)	Allowable deflection at 100Pa (mm)
		1	2	3	4	5	6		
100	1	2.4	2.0	6.4	3.0	2.4	0.2	4.8	4.8

N.B. The allowable deflection is in accordance to TME and equal to 1/25th of width.

4.2 Test Result of air leakage

Duct Size (mm)	Pressure (Pa)	Square Area (Sq. Meter)	Test Leakage (Liter/Sec)	Max. Allowed Leakage (Liter/Sec)
100 x 500	100	10.0	1.0	2.0


N.B. The allowable air leakage is in accordance to TME and equal to 40% of maximum permitted limit for the appropriate pressure class, as indicated in Table 17 of DW144.

5. CONCLUSION

As shown in section 4 "Results", test specimen does not exceed the deflection and air leakage requirement of DW144 (specification for sheet metal ductwork 1998) and TME (1987) as stipulated.

CHECKED BY:

Yale Wang
Yale Wang
For and on behalf of:
Campbell Shillinglaw Lau Ltd.





插式法蘭測試報告

Model:M-140

Campbell Shillinglaw Lau Ltd
金寶聲學環保顧問有限公司

Our Ref: CSLL019-2010100901R_1a

REPORT ON DEFLECTION OF DUCTWORK TEST

TO
DW144 (SPECIFICATION FOR SHEET METAL DUCTWORK 1996)
FOR MEDIUM PRESSURE SYSTEM

ON
MYG-140 SLIDE ON FLANGE SYSTEM & STIFFENER SYSTEM
(CLASSIFICATION TO TM1)

DATE : 1ST SEPTEMBER 2010
TESTED BY : MR. WILSON LEUNG (CSLL)
REPORT BY : MR. LESLIE LAU (CSLL)
SPONSOR OF TEST : MYG INTERNATIONAL LIMITED
TEST LOCATION : MYG FACTORY
WABIA CENTRE ROAD
LANGKOA INDUSTRIAL AREA
QIAO YOU TOWN
DONG GUAN CITY
GPC

The A 157, Midland Commercial Building, 25-26 The Avenue, Tsim Sha Tsui, Kowloon, Hong Kong
香港九龍彌敦道中環大廈第25、26號中環商業大廈A157
Tel: (852) 400-2228/2621 Fax: (852) 400-2827/2626 Email: leslie.lau@campbellshillinglaw.com.hk

1. INTRODUCTION

Campbell Shillinglaw Lau Limited were commissioned by MYG International Limited to carry out duct deflection behavior test on their MYG-140 slide on flange stiffener and flange joint system in accordance with DW144 (Specification for Sheet Metal Ductwork, 1996) and TM1.

2. TEST APPARATUS

a) The Test apparatus consists primarily of the following:-
i) a centrifugal flow fan,
ii) a bypass damper,
iii) A U-tube manometers giving readings of the differential pressure between the sheet metal duct assembly and the ambient,
iv) a flexible hose connecting the connecting the fan-duct assembly to the sheet metal duct,
v) a dial gauge giving readings of 0.01mm resolution and a maximum traverse of 50mm.

The overall experimental set up is as shown in 100901A.1 and 100901A-2 and the detail set up for the deflection measurement is as shown in 100901B.

3. TEST SAMPLE

The test specimen of the following dimension, 100901C, were constructed:
Specimen: 2540 mm (L) x 4000 mm (W) x 1000 mm (H), tie rod used on the mid-span of duct flange system and duct stiffener system (Rated to 36 medium pressure)

The test sample consists of a rectangular duct (1.2 mm thick) which was prefabricated by pitburg lock seam, 100901D, and ready for duct section assembly.

The MYG-140 flange was made by a ACL machine (100901E). The corner piece used to connect the flange is shown in Appendix 1.

The MYG-140 slide on flange was fastened to the duct section to form a cross joint by spot welding details as follows:

1. Duct flange system using the spot welding at 50mm from corners and 150mm O.C. for the rest.

2. Duct flange system using the spot welding at 50mm from corners and 300mm O.C. for the rest.

Configuration of the flange joint, flange stiffener, the sheet metal duct and the G-clamp are as shown in 100901E.

4. RESULTS

4.1 - Deflection Results at Flange Stiffener

Dial Gauge Reading	Pressure (Pa)						Calculated Deflection @ 100Pa (mm)	Allowable Deflection (TM1) (mm)
	0	500	1k	1.5k	2k	0		
Specimen	0	1.75	5.5	5.72	5.31	1.82	0.1	3.28

4.2 - Deflection Results at Flange Joint

Dial Gauge Reading	Pressure (Pa)						Calculated Deflection @ 100Pa (mm)	Allowable Deflection (TM1) (mm)
	0	500	1k	1.5k	2k	0		
Specimen	0.18	2.78	5.08	5.25	5.76	2.70	0	8.0

5.B. The allowable deflection is in accordance to TM1 and equal to 1/250 of width or where tie rods are used, 1/250 of span between central tie rod and the side of the duct.

5. CONCLUSION

As shown in "Section 4 Results", deflection at flange joint and flange stiffener did not exceed the requirement of TM1 as stipulated.

TEST AND REPORT BY

Leslie Lau
For and on behalf of
Campbell Shillinglaw Lau Ltd.

